

TO:

API NUMBER 15- 207-19007-00-00

STATE CORPORATION COMMISSION 4-9

NW, SEC. 27, T 25 S, R 17 E

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MOON/BENNETT WELL # 48

TECHNICIAN'S PLUGGING REPORT

COUNTY WOODSON

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 750 FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. WELL SERVICE LICENSE NUMBER 3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 1:00PM DAY: 9 MONTH: 4 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM C.P. TITEL

(COMPANY NAME) KCC (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT WAS CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 9 MONTH: 4 YEAR: 98

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 2" ANNULUS AT SURFACE. 1" PIPE WAS WASHED TO 500' IN THE 2" AND 8" ANNULUS. CEMENT WAS PUMPED INTO THIS 1" UNTIL CEMENT CIRCULATED FROM THE 2" AND 8" ANNULUS AT SURFACE. ALL 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 126 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS: Control# 19980029-048

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel

(TECHNICIAN)

FORM CP-2/3