

1060390

15-145-30013-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 6-3-65

C SW NE, SEC. 31; T 22 S, R 16 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Pike Well # 1

Operator: Halliburton Oil Producing Co.  
Name & Address: 2915 Classen Blvd.  
Oklahoma City, OK 73106

County Pawnee

Well Total Depth 4182 135.92 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 2 Month: November Year: 1984

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4182' Perfs at 4117-23'

1st plug sand back to 4070' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel 70 sx cement, 10 sx gel and released

8 5/8" rubber plug and pump 125 sx cement

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1984

11-8-84 CONSERVATION DIVISION Wichita, Kansas

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00 am Day: 2 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4182' Perfs at 4117-23'

1st plug sanded back to 4070' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel and released

8 5/8" rubber plug and pumped an additional 125 sx cement

Maximum pressure 500 psi and shut in pressure 100 psi

Remarks: Recovered 2280' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

Signed Paul A. Luthie (TECHNICIAN)

INVOICED  
DATE 11-19-84  
INV NO. 4791