

43

64
R

To: 1-120394
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,064-0000

S/2 SW NE, SEC. 29, T 22 S, R 15 WAE
2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3517

Lease Name Fox Well # D-1
County Pawnee 131.63

Operator: Columbian Services Corporation
Name & Address Bank IV Tower
Box 3501
Topeka, KS 66601-3501

Well Total Depth 4050 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 605

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 3 Month: 4 Year: 1990

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 2996' w/100 sx cement Perfs at 2867-75'
1st plug sand back to 2810' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 3 Month: 4 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 2810' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

APR 06 1990

DATE APR 13 1990

INV. NO. 27838

CONSERVATION DIVISION
WICHITA, KANSAS
41-6-90

Signed Steve Durrant
(TECHNICIAN)