

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009 -23,491 0000
SE NE SW Sec. 32, T 16 S, R 11 (W)K
1650 feet from ~~XX~~S section line
2310 feet from W/~~X~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Hitschmann Estate Well # 11

Operator: National Cooperative
Name & Refinery Association
Address Box 6
Great Bend, Ks. 67530

County Barton

Well Total Depth 3345 feet 108.72
Conductor Pipe: Size 0 feet
Surface Casing: Size 8^{5/8} feet 397

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929 Tag # 466

Address Box 823 Great Bend, Ks.

Company to plug at: Hour: 5 PM Day: 11 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Bill Draney

(company name) Duke Drilling Company Inc (phone) (316) 793-7824

were: 8^{5/8}" 397' S.P. CUC w/250 sks common 3% ^{CA-CL.} gel by Sun Cementing Ordered 190 sks

50/50 pozmix 4% gel 3% cal. cl.-1 sk cello-flake, and 8^{5/8}" plug. Spot with drill

stem- turn hole over, heavy mud between all plugs. Arbuckle @ 3335' Elev. 1895,

Anhy 746 No circulation problems.

Signed Marion Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 PM Day: 11 Month: April Year: 19 84

ACTUAL PLUGGING REPORT Ordered 190 sks 50/50 pozmix 4% gel 3% cal. cl. 1 sk cello-

flake and 8^{5/8}" plug. Spotted with drill stem, truned hole over, heavy mud between

all plugs. 1st plug @ 3300' w/25 sks cmt

2nd plug @ 750' w/25 sks cmt

3rd plug @ 570' w/80 sks cmt w/1 sks cello-flake

4th plug @ 240' w/40 sks cmt

5th plug solid bridge hull's and plug @ 40' to 0 w/10 sks cmt

Remarks: 10 sks in Rat Hole (circulate) Cemented by Allied

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Marion Schmidt
DOIC (TECHNICIAN)

INVOICED

DATE 4-23-84

INV. NO. 1234