

11-18

To: 6 061716
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,361 0000
NE 32 16 11
SEC. T S, R W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5230
Operator: Petroleum Energy Inc.
Name & Address: 224 East Douglas
Wichita, Ks. 67202

Lease Name Rous C Well # 1
County Barton 109.85
Well Total Depth 3380 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address Great Bend, Ks. 67530 Box 768

Company to plug at: Hour: 9:00AM Day: 18 Month: Nov Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone)

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal C1 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

12-29-88

CONSERVATION DIVISION
Wichita Kansas

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 18 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 346' w/200 sks. 5 1/2" set at 3380'

w/150 sks. Top perf at 2986'. Plugged bottom w/sand and 5 sks cement to 2940'.

Shot pipe three times and recovered 1496'. Rumped in 8 5/8" 25 sks cement

followed w/5 sks Hulls in 175 sks cement w/800 psi.

Remarks: By Halliburton Ran line to 900'.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby authorize to reserve this plugging.

DATE 1-5-89

INV. NO. 23502

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck FORM CP-2/3 Rev. 01-84