

15-009-03169-0000

57

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API-NUMBER 15-

SE NESE, Sec. 32, T 16 S, R 11 W 10

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5064

Lease Name Hitchman C Well # 2

Operator: Sierra Petroleum Co., Inc.
Name & Address 211-N. Broadway, Wichita, Ks.
67202

County Barton

Well Total Depth 3334 feet \$108.34

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 297'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelco Logging Pulling License Number 6050

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 9 Month: 6 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelco

(company name) Kelco Logging Pulling (phone) 316-938-2457

were: Order 167 lbs. 50 gr. mix - 4% Gel. - 3% Cal. U., 5 lbs. hulls,
15 lbs. Gel. + 8 5/8" plug.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 AM Day: 9 Month: 6 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 297' cas. w/ 150 lbs. 5 1/2" set at 3395 w/ 80 lbs. Top perf at 3030'. Plugged bottom w/ placement, sand & 5 lbs. cement to 3000'. Shot pipe 3 times & recovered 2305'. Pumped in 8 5/8", 4 lbs. hulls, 12 lbs. Gel., 65 lbs. cement, 3 lbs. Gel., 1 lb. hulls, released plug & followed w/ 100 lbs. cement w/ 1000 pounds pressure.

Remarks: By Allied Cementing Co. Inc.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

Signed [Signature] (TECHNICIAN)

FORM CP-2/3 Rev. 9-82

INVOICED

DATE 6-20-83

JUN 13 1983

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 4624-W