

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER 15-205-19813-00-00
 SE NE SE Sec/Twp/Rge Sec 9 T29S R17E
1515 (GPS) feet from south section line
513 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
 Lease/Well# Stich North - Wiles gps# STI 03
 Operator License # 101 County Wilson
 Operator: State Of Kansas Fee Fund Well Total Depth 850 (est) feet
 Name & Stich North Project Production Pipe: 2 Size Feet NA
 Address _____ Surface Casing: NA Size Feet NA
 AB oil well XXXXXX Gas Well _____ SWD Well/ Input Well _____ D & A _____
 Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097
 Address: 19450 Ford Road, Chanute, Kansas 66720
 Company to plug at: _____ Hour: _____ Day: 29 Month: 7 2009
 Plugging proposal received from: Sam Kepley
 Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730
 Were: Wash well to TD and fill from btm to top with portland cement.

Plugging Proposal Received by: Alan M. Dunning
 Plugging attended by Agent: All XXXXXX Part _____ TECHNICIAN
 Operations Completed: Hour: _____ Day: 29 Month: 7 2009
 Actual Plugging Report: 3' of 10" surface pipe was set to bring well to surface. A 1" pipe was
lowered to 600' The 1" pipe was removed and the well was perforated at 600', 300, and 150'. A 1" cement
string was lowered to 650' inside the 2" pipe. The well was pumped full of cement from btm to top thru this
cement string. A total of 28 sacks of portland cement were to plug well. The well was cut off below plow
depth and the location restored.

Remarks: Control # 20090028-003
 (If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Alan M. Dunning
 TECHNICIAN