

1050469

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-20,931-0000

C S/2 S/2 NE SEC. 10, T 22 S, R 23 W/R

2970 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Bamberger "A" Well # 2

Operator: Raymond Oil Company, Inc.

County Hodgeman 149.92

Name & Address One Main Place, Suite 900

Well Total Depth 4613 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 441

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4:00 pm Day: 4 Month: March Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4610' Open Hole

1st plug sand back to 4550' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:00 pm Day: 4 Month: March Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4550' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Cement top dropped 640'. Filled back up with redi-mix (3-6-85)

RECEIVED  
STATE CORPORATION COMMISSION  
3-15-85

Maximum pressure 800 psi and shut in 100 psi

MAR 15 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2792' 4 1/2" casing.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

UNVOICED

(If applicable) observe this plugging.

DATE 3-18-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 7372 APR 10 1985

3-4