

1050470

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-20,793-0000
of C NE SE
200' NW, SEC. 10, T 22 S, R 23 W/X
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Bamberger Well # 1

Operator: Raymond Oil Company, Inc.

County Hodgeman 150.97

Name & Address One Main Place, Suite 900

Well Total Depth 4645 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 4 Month: March Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" set at 4644' Open Hole

Pump 150 pounds of hulls, 50 sx cement, 9 sx gel, 10 sx cement down 4 1/2"-pressure up
Squeeze 4 1/2" x 8 5/8" annulus from 900' to surface.

RECEIVED
STATE CORPORATION COMMISSION

3-11-85 MAR 11 1985

Plugging Proposal Received by Richard W. Lacey
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 pm Day: 4 Month: March Year: 1985

ACTUAL PLUGGING REPORT Pumped 150 pounds of hulls, 50 sx cement, 9 sx gel, and

10 sx cement down the 4 1/2". Maximum pressure 1800 psi and shut in 1000 psi

Squeezed 4 1/2" x 8 5/8" annulus from 900' to surface. Cement dropped 46'.

Filled back up with redi-mix (3-6-85)

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(old / ~~xxx~~) observe this plugging.

DATE 3-12-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 7324