

9-4

1 051085

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,309-0000
75' W SE NE SE, SEC. 10, T 22 S, R 23 W/E
1650 feet from S section line
405 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418
Operator: Allen Drilling Company
Name & Address: P.O. Box 1389
Great Bend, KS 67530

Lease Name Bamberger Well # 1-10
County Hodgeman 150.15
Well Total Depth 4620 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 416

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 4 Month: 9 Year: 19 88

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-5877

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1573-1606'

1st plug at 1600' with 50 sx cement, 2nd plug at 800' with 70 sx cement,

3rd plug at 440' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3 p.m. Day: 4 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement,

2nd plug at 800' with 70 sx cement,

3rd plug at 440' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

DATE 9-14-88

INV. NO. 22224

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1988
CONSERVATION DIVISION
Wichita, Kansas
9-12-88

SPD