

To: 1 080120 5-13

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 145-01,011-0002
SW SW NE, SEC. 28, T 22 S, R 16 XX
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 6039
Operator: L.D. Drilling, Inc.
Name & Address
RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Peters Trust Well / 1-OWWO
County Pawnee 101.53
Well Total Depth 3124 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 7 P.m. Day: 13 Month: 5 Year: 19 97

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe 5-16-97
1st plug at 1000' with 50 sx cement, 2nd plug at 450' with 50 sx cement,
3rd plug at 260' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:45 p.m. Day: 13 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement,
2nd plug at 450' with 50 sx cement,
3rd plug at 260' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(XXXX) did not observe this plugging.

DATE MAY 20 1997

Signed Kevin D. Shute (TECHNICIAN)

INV. NO. 48129
5-13

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 4-22-97

State of Kansas

15-

145-01,011-0002

FORM MUST BE TYPED

DISTRICT #

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

ALL BLANKS MUST BE FILLED

Expected Spud Date: May 1 1997

Spot SW - SW - NE. Sec. 28. Twp. 22. S, Rg. 16. East

OPERATOR: License # 6039
Name: L.D. DRILLING, INC.
Address: R.R. 1 BOX 183 B
City/State/Zip: GREAT BEND, KANSAS. 67530
Contact Person: L.D. Davis
Phone: (316) 793-3051

2970 feet from South / North line of Section
2310 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 6039
Name: L.D. Drilling, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Pawnee
Lease Name: Peters Trust Well #: L.O.W.D.
Field Name:

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
X O.W.D. ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Is this a Prorated/Spaced Field? X yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 2047 330'

if O.W.D.: old well information as follows:
Operator: ARMER, INC.
Well Name: Peters #1
Comp. Date: 2-12-54 Old Total Depth: 4170

Ground Surface Elevation: 2047 feet MSL
Water well within one-quarter mile: X yes ... no
Public water supply well within one mile: X yes X no

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 210'
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe: has 230'

Exp. 10/17/97

AFFIDAVIT

230' Alt. H set

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Plugged Well

Pusher Greg Davidson INIT. R.L.
SPUD DATE 5-11-97
LENGTH SURFACE PLANNED 2300' 85%
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE @ CONDUCTOR
ANHYDRITE T B ELEVATION
TD 3124 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1000 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ 450 Ft. W/ 50 SX
Bottom Surface @ 260' Ft. W/ 40 SX
40' Plug @ 40' Ft. W/ 10 SX
RAT HOLE CIRC/W SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN G.W. DATE 5-14-97
TYPE OF CEMENT 60/40 6% #4 Flow
STARTING TIME 7:00 (AM/PM) DATE 5-13-97
COMPLETION TIME 8:45 (AM/PM) DATE 5-13-97
CEMENT COMPANY Allied #4570