

To: 1 030845
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4752

Operator: Source Petroleum
Name & Address: 910 Century Plaza Building
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 11 p.m. Day: 1 Month: 9 Year: 19 87

Plugging proposal received from Don Kern

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1888'
Anhydrite 755'

1st plug at 3859' with 50 sx cement, 2nd plug at 755' with 40 sx cement,

3rd plug at 298' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:45 a.m. Day: 2 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3859' with 50 sx cement,

2nd plug at 755' with 40 sx cement,

3rd plug at 298' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Water well plugged with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If you did not observe this plugging.

DATE 9-4-87

INV. NO. 18055

9-2
API NUMBER 15- 185-22,457-0000

SW SW NW, SEC. 23, T 22 S, R 13 W/E
2970 feet from S section line
4950 feet from E section line

Lease Name Krankenberg "A" Well # 1

County Stafford 127.43

Well Total Depth 3921 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

9-3-87
STATE CORPORATION COMMISSION
SEP 3 1987
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 8 30 87
month day year

API Number 15- 185-22,457-0000

OPERATOR: License # 4752
Name Source Petroleum
Address 910 Century Plaza Building
City/State/Zip Wichita, Kansas 67202
Contact Person John D. Howard, Jr.
Phone (316)-262-7397

SW SW NW Sec. 23 Twp. 22 S, Rg. 13 East
2970' Ft. from South Line of Section
4950' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5418
Name Allen Drilling
City/State Great Bend, Kansas

Nearest lease or unit boundary line 330 feet
County Stafford

Lease Name Krankenbergs "A" Well # 1
Ground surface elevation 1888 feet MSL

Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Depth to bottom of fresh water 80

Depth to bottom of usable water 240

Surface pipe by Alternate: 1 2

Surface pipe planned to be set 240'

Conductor pipe required N/A

Projected Total Depth 3900 feet

Formation Arbuckle

If OWWO: old well info as follows:

Operator
Well Name
Comp Date
Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8-17-87 Signature of Operator or Agent John D. Howard, Jr. Title Biologist/Partner

For KCC Use:

Conductor Pipe Required 240 feet; Minimum Surface Pipe Required 240 feet per Alt.

This Authorization Expires 2-25-88 Approved By Pat 8-25-87

*SPUD 8-26-87
8578-260 Steve*

SW SW NW Sec. 23 Twp. 22 S, Rg. 13 East
 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @	<u>Arbuckle</u>	feet depth with	<u>50</u>	sxs of	<u>60/40</u>
2nd plug @	<u>Base Anhydrite</u>	feet depth with	<u>40</u>	sxs of	<u>60/40</u>
3rd plug @	<u>30' below sur. case</u>	feet depth with	<u>50</u>	sxs of	<u>60/40</u>
4th plug @	<u>40</u>	feet depth with	<u>10</u>	sxs of	<u>60/40</u>
5th plug @		feet depth with		sxs of	
(2) Rathole with	<u>15</u>	sxs		(b) Mousehole with	<u>10</u> sxs

PUSHER Don Ken

TD 3920 FORMATION 3853 - Arb.

SURFACE PIPE 8 7/8 @ 260

ANHYDRITE Base ELEVATION 1888

STARTING TIME & DATE 11:00 AM - 9-1-87

COMPLETION TIME & DATE 3:45 AM 9-2-87

1st PLUG @ 3859 FT. W/ 50 SX

2nd PLUG @ 755 FT. W/ 40 SX

3rd PLUG @ 299 FT. W/ 50 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 15 SX

WATER WELL PLUGGED W/ 5 SX SX

CEMENT COMPANY B. J. Tite w.w.

TECHNICIAN

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1987
CONSERVATION DIVISION
Wichita, Kansas