

6-16-88

167 R

To: 1 061108  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-20,334-0000  
SE SE NE, SEC. 34, T 22 S, R 16 (W) X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

2970 feet from S section line

330 feet from E section line

Operator: Halliburton Oil Producing Company  
Name & Address: Box 10  
Stafford, KS 67578

Lease Name Milburn Well # 1

County Pawnee 131.98

Well Total Depth 4061 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 16 Month: 6 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4059' PBD 4049' Perfs at 3992-4006'

1st plug sand back to 3940' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 16 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3940' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2762' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this report.)

(If used, use this to observe this plugging.)

INVOICED

DATE 7-13-88

INV. NO. 21322

Signed Paul A. Luthi (TECHNICIAN)

RECEIVED 6-21-88  
STATE CORPORATION COMMISSION  
JUN 21 1988