

02- 40975

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20644-00-00 Spot: NW NW SW
Sec: 29 Twnshp & Dir: 22 S Rng & Dir: 3 W
Feet: 2310 frm N/S: S Feet: 3960 frm E/W: E
Lease/Unit Name: SCHMIDT Well Number: L-1
County: HARVEY Total Vertical Depth: 123.05 feet

Operator License No.: 6804
Operator Name: Lachenmayr Oil Co.
Address: 904 Emmaline
Newton, KS 67114

8/8

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 658
Production: Size 5.5 feet: 3786

123.05

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/08/2000 3:30 PM
Plug Co. License No.: 32147 Plug Co. Name: K.E. Snyder Co., LLC
Proposal Received from: Howard Lachenmayr Company Name: SAA
OpRepPhoneNo: (316) 284-7150

Were: Sand to 3700' and 5sxs of cement. 50sxs of cement @ 740'. Circulate cement from 320'.

Plugging Proposal Received By: District 2 Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/08/2000 3:30 PM

Actual Plugging Report:

The perms were covered w/sand to 3700' and capped w/5sxs of cement. The 5 1/2 was recovered from 1492' and pulled to 740', where 50sxs of cement was spotted. The pipe was pulled to 320' where cement was circulated to surface.

RECEIVED
KCC DISTRICT #2

AUG 11 2000

WICHITA, KS

Remarks: United cementing 60/40 4%gel

Anhydrite Plug: No

Bottom Plug:

Dakota Plug: No

Plugged through:

I (did / did not) observe this plugging.

INVOICED Signed

(TECHNICIAN)

DATE 8/18/00

WV. NO. 1060430