

1 120306

9-13

141 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,330-0006  
150' S of  
C. NW NE, SEC. 24, T. 22 S, R. 22 W/EX

4470 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Anna Webster Well # 1

Operator: Ritchie Exploration, Inc.

County Hodgeman 143.98

Name & Address 125 North Market, Suite 1000

Well Total Depth 4430 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1301

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 12 Month: 9 Year: 19 89

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1330' with 50 sx cement, 2nd plug at 420' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 a.m. Day: 13 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1330' with 50 sx cement, 9-28-89

2nd plug at 420' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-#-89

Signed [Signature]  
(TECHNICIAN)

INV. NO. 26021

15- 083-21,330-0000

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ..... August 30 1989 .....  
month day year

150' S of  
C. NW NE ..... Sec .24' Twp .22 S, Rg .22. X East  
West

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: 125 N. Market, Suite 1000  
City/State/Zip: Wichita, KS 67212  
Contact Person: Rocky MILFORD  
Phone: 316/267-4375

.....4470..... feet from South line of Section  
.....1980..... feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 6033  
Name: Murfin Drilling Co.

County: Hodgeman  
Lease Name: Anna Webster Well #: 1  
Field Name: (Hanston-Opdy) UNKNOWN

Is this a Prorated Field? ..X.. yes .. no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 660'

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWM ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes

Ground Surface Elevation: 2138 feet MSL  
Domestic well within 330 feet: .. yes ..X.. no  
Municipal well within one mile: .. yes ..X.. no

Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 300'  
Surface Pipe by Alternate: ..X.. 1 .. 2  
Length of Surface Pipe Planned to be set: 1300'

If OWM: old well information as follows:  
Operator: .....  
Well Name: .....  
Comp. Date: ..... Old Total Depth .....

Length of Conductor pipe required: .....  
Projected Total Depth: 4450'  
Formation at Total Depth: Mississippian

Water Source for Drilling Operations:  
... Well ... farm pond X other

Directional, Deviated or Horizontal wellbore? .... yes ..X.. no  
If yes, total depth location: .....

OUR Permit #: .....  
Will Cores Be Taken?: .... yes ..X..no  
If yes, proposed zone: .....  
360' Alt. I Req.

878 @

AFFIDAVIT

PUSHER Drillet Lloyd Ablect  
TB 430 FORMATION MISSISSIPPI  
SURFACE PIPE 878 @ 1301  
ANHYDRITE \_\_\_\_\_ ELEVATION \_\_\_\_\_  
STARTING TIME & DATE 10<sup>20</sup> 9-12-89  
COMPLETION TIME & DATE 12<sup>30</sup> 9-13-89

1st PLUG @ 1330 FT. W/ 50 SX  
2nd PLUG @ 420 FT. W/ 30 SX  
3rd PLUG @ 40-0 FT. W/ 10 SX  
4th PLUG @ \_\_\_\_\_ FT. W/ \_\_\_\_\_ SX  
RAT HOLE CIRCULATED W/ 15 \_\_\_\_\_ SX  
MOUSE HOLE CIRCULATED W/ 10 \_\_\_\_\_ SX  
WATER WELL PLUGGED W/ Creek - \_\_\_\_\_ SX

CEMENT COMPANY allied  
TECHNICIAN \_\_\_\_\_  
TYPE OF CEMENT 6017 @ Pot

RECEIVED  
CORPORATION COMMISSION  
SEP 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

5280	1980
4950	1650
4620	1320
4290	990
3960	660
3630	330
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Wichita, Kansas Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

REMEMBER TO:

- file Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- file acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.