

1050468

Docket No. D-20,833

API NUMBER 15- 083-20,840.00.00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NE, SEC. 10, T 22 S, R 23 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Babmerger "A" Well # 1 SWD

Operator: Raymond Oil Co., Inc.

County Hodgeman 150.97

Name & Address One Main Place, Suite 900

Well Total Depth 4645 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 409'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 354, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 4 Month: March Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) 316-938-2457

ware: 4 1/2" set at 4644' Open Hole

1st plug pump 50 sx cement, 15 sx gel, and 100 sx cement down 4 1/2"

2nd plug pump 1 sack hulls and 80 sx cement down 4 1/2" x 8-1/2" annulus

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 pm Day: 4 Month: March Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement, 15 sx gel and 100 sx cement down 4 1/2" casing. Maximum pressure 500 psi and shut in 100 psi

2nd plug pumped 1 sack hulls and 80 sx cement down 8 5/8" x 4 1/2" annulus 3-11-85

Maximum pressure 700 psi and shut in 500 psi

RECEIVED STATE CORPORATION COMMISSION

Cement dropped 216'. Filled back up with redi-mix (3-6-85)

MAR 11 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

(if did not) observe this plugging.

DATE 3-12-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 7323