

To: 1 090526 3-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15.083.10268.00.01  
API NUMBER 15- 11/8/62  
C SE SW, SEC. 17, T 22 S, R 22 W/EX  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5363  
Operator: BEREXCO INC.  
Name & Address P.O. Box 723  
Hays, KS 67601

Lease Name Dan Ewy Well # 3  
County Hodgeman 148.36  
Well Total Depth 4565 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BEREXCO INC. License Number 5363  
Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 1:30 p.m. Day: 21 Month: 3 Year: 19 95

Plugging proposal received from George  
(company name) BEREXCO INC. (phone) 913-628-6101

were: 5 1/2" at 4564' with 125 sx cement, Perfs at 3811-41, 4340-50, 4355-58, 4360-66, 4404-08, 4470-82, Sq. 3811-41' w/25 sx cement

1st plug pump 2 sx hulls and 25 sx cement on bottom,  
2nd plug perforate at 650' and pump 200 sx cement.  
Check backside.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 24 1995  
3-24-95

Plugging Proposal Received by STEVEN W. BILFINGER  
WICHITA, KS (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:45 p.m. Day: 21 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 3 sx hulls and 40 sx cement,  
2nd plug pumped down 5 1/2" casing with 40 sx gel to 675', perforated casing at 650' and  
pumped in 135 sx cement. Maximum pressure 1800 psi and shut in 150 psi.  
3rd plug hooked onto backside and pumped in 80 sx cement. Maximum pressure 500 psi and  
shut in 320 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

I (and my employees) observe this plugging.

INVOICED  
DATE MAR 30 1995  
INV. NO. 42481

Signed [Signature]  
(TECHNICIAN)