

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

			X

Locate well correctly on above
Section Plat

Hodgeman County, Sec. 11 Twp. 21S Rge. 26W (E) (W)
 Location as "NE/CNW&SW" or footage from lines. C NE NE
 Lease Owner Sunray DX Oil Company
 Lease Name Joe Clifton Well No. 1
 Office Address 321 West Douglas, Wichita, Kansas (67202)
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 19
 Application for plugging filed January 2 19 64
 Application for plugging approved January 6 19 64
 Plugging commenced January 2 19 64
 Plugging completed January 2 19 64
 Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas
 Producing formation Depth to top Bottom Total Depth of Well 4585 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	water	4434	T.D.	8-5/8"	282'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from total depth to 700' and placed 25 sacks of cement at 700'.
 Filled hole with mud, to 270' and placed 25 sacks of cement at 270'. Placed 10 sacks of cement to surface. Placed 5 sacks of cement in rat hole and mouse hole. Well plugged and abandoned 1-2-64.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1964
1-15-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
 Address 1100 Bitting Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 Gary W. Pierce (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce
 321 West Douglas, Wichita, Kansas (67202)
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 64

My commission expires July 13, 1967

Wm. [Signature]
 Notary Public.

Sunray L& Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
January 8, 1964

Contractor: Stickle Drilling Company
Date Commenced: December 22, 1963
Date Completed: January 3, 1964

Joe Clifton No. 1
NE NE Sec. 14-21S-26W
Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Post rock:	60
Shale and shells	1303
Red beds	1523
Anhydrite	1642
Red beds and shells	1875
Shale and lime	2790
Broken lime	2925
Shale and lime	3325
Shale	3700
Lime	3873
Shale and lime	4050
Lime	4160
Cherty lime	4253
Lime	4388
Sand, chert and shale	4415
Lime	4446
Lime and chert	4471
Lime	4505 TD

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray L& Oil Company's Joe Clifton No. 1, NE NE Section 14-21S-26W, Hodgeman County, Kansas.

Fred E. Stickle
FRED E. STICKLE

W. Mensley
Notary Public

My Commission Expires January 11, 1967.