


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 2 Twp. 21S Rge. 26W(E) (W)
Location as "NE/CNWxSWx" or footage from lines NW SW
Lease Owner Frontier Oil Company
Lease Name Sinclair Well No. 1
Office Address 1720 Wichita Plaza, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed June 26 19 63
Application for plugging filed June 26 19 63
Application for plugging approved June 26 19 63
Plugging commenced June 26 19 63
Plugging completed June 26 19 63
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4552 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	360'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300'
set plug, 1/4 sx hulls, 20 sx
cement. Filled hole with mud
up to 40', set plug, 1/4 sx
hulls 10 sx cement. 2 sx cement
in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Co.
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George A. Angle (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
1720 Wichita Plaza, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 63

Doraine V. Head
Notary Public.

My commission expires 11-17-66

15.083.10056.00.00

DRILLERS LOG

Sinclair #1

CASING RECORD: 8 1/2" @ 360' w/185 sx cement
 COMPANY: Frontier Oil Company
 CONTRACTOR: Red Tiger Drilling
 COMMENCED: June 13, 1963
 COMPLETED: June 26, 1963

DESCRIPTION: NW SW
 2-21S-26W
 Hodgeman Co.,
 Kansas

ELEVATION: 2401 DF
 2405 RB

TOTAL DEPTH: 4552'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Soil, Clay & Sand	0	40
Shells & Shale	40	75
Shale, Shells & Gravel	75	365
Shale, Shells & Redbed	365	1080
Sand	1080	1290
Shale & Shells	1290	1550
Shale	1550	1589
Anhydrite	1589	1630
Shale & Shells	1630	2035
Shale & Lime	2035	2615
Lime	2615	2710
Lime & Shale	2710	3702
Lime	3702	4229
Lime & Chert	4229	4320
Lime	4320	4380
Lime & Sand	4380	4385
Chert	4385	4408
Lime	4408	4552

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 8 1963
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle

 George A. Angle

Subscribed and sworn to before me this 3rd day of July, 1963.

Doraine V. Head

 Notary Public

My Commission Expires:

11-17-66