


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 15 Twp. 22 Rge. 22 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE SW
Lease Owner Beardmore Drilling Company
Lease Name Huling Well No. 2
Office Address 827 Beacon Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-1 19 63
Application for plugging filed 10-1 19 63
Application for plugging approved 10-1 19 63
Plugging commenced 10-1 19 63
Plugging completed 10-2 19 63
Reason for abandonment of well or producing formation Crooked hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1278 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM'	TO	SIZE	PUT IN	PULLED OUT
Clay		0	40		None	
Sand and shale		40	875		"	
Sand		875	900		"	
Red beds, shale		900	1195		"	
Shale		1195	1278		"	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0 to 180' - 325 sacks cement
180' - wood plug
180' to 400' - heavy mud
400' to 690' - 100 sacks cement
690' - wood plug
690' to 1278' - heavy mud

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1963
CONSERVATION DIVISION
Wichita, Kansas
10-14-1963

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 514 Orpheum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
827 Bacon Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 63
Shirley Ann Jackson
Shirley Ann Jackson Notary Public.
My commission expires 7-13-67

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

CONSERVATION DIVISION
Wichita, Kansas

HULING #2
C SE SW SECTION 15-21S-21W
HODGEMAN COUNTY, KANSAS


COMMENCED: SEPTEMBER 30, 1963
COMPLETED: OCTOBER 2, 1963

OPERATOR - BEARDMORE DRILLING Co.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	40	CLAY	
40	875	SAND & SHALE	
875	900	SAND	
900	1195	RED BED, SHALE & SHELLS	
1195	1264	SHALE	
1264	1278	SHALE	
1278	TD		

DRY & ABANDONED
FILLED HOLE WITH HEAVY MUD TO 690 FEET. SET PLUG WITH 100 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 180 FEET. SET PLUG WITH 325 SACKS CEMENT. CEMENTED FROM 180 FEET TO BOTTOM OF CELLAR. PLUGGING COMPLETED AT 2:30 A.M. OCTOBER 2, 1963.

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C SE SW SECTION 15-21S-21W, HODGEMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.



E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 7TH DAY OF OCTOBER, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.


VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967.