

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 13 Twp. 21S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines. C NE NE

Lease Owner Rains & Williamson Oil Co.

Lease Name SCHRAEDER Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-21 19 63

Application for plugging filed 9-21 19 63

Application for plugging approved 9-21 19 63


Plugging commenced 9-21 19 63

Plugging completed 9-21 19 63

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities

If a producing well is abandoned, date of last production ----- 19 ---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas

Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 4490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	238'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud, set first plug at 700' and pumped 25 sacks cement. Filled hole with rotary mud, set second plug at 230'. Pumped 25 sacks cement. Filled hole with rotary mud to 40'. Set plug and hulls and capped with 15 sacks cement. Plugging completed at 10:00 A.M., September 21, 1963.

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Building - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains

(Signature) Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains, Partner
1425 Wichita Plaza Bldg. - Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of September, 19 63

My commission expires November 8, 1966

Sherry Gish Notary Public.

15.083.10228.00.00
ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.
#1 SCHRAEDER
C NE NE Sec. 13-21S-25W
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.
COMMENCED: 9-7-63
COMPLETED: 9-21-63

Remarks: Set 8-5/8" surface casing at 238' with 125 sacks quick cmt.

Formations

Surface Clay	35'
Sand	45'
Shale	630'
Red Bed and Shale	915'
Anhydrite	945'
Shale	1010'
D. Sand	1215'
Shale	1400'
Shale and Shells	1540'
Anhydrite	1575'
Shale and Shells	2200'
Shale and Lime	2395'
Lime and Shale	3155'
Shale and Lime	3600'
Lime and Shale	3860'
Lime	4230'
Lime and Shale	4270'
Lime	4396'
Lime and Shale	4414'
Lime	4422'
Lime and Shale	4430'
Lime	4440'
Lime and Shale	4460'
Lime	4490'

Rotary Total Depth (D&A) 4490'


RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1963
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 24th day of September, 1963.


Sherry Glah Notary Public

My Commission Expires: Nov. 8, 1966