

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15.083.10168.00.00
WELL PLUGGING RECORD

NORTH

Locate well correctly on above Section Plat

Hodgeman County, Sec. 21 Twp. 22 Rge. 23 (E) (W)
 Location as "NE/CNW/SW" or footage from lines NW NW NW
 Lease Owner Joseph E. Newman
 Lease Name Schneider Well No. 1
 Office Address 2005 Tower Denver U.S. Nat. Center Denver 2, Colo.
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 1-13-61 19__
 Application for plugging filed 12-5-60 19__
 Application for plugging approved 12-5-61 19__
 Plugging commenced 1-10-61 19__
 Plugging completed 1-13-61 19__
 Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19__
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4728 1/2 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 4600' mix and dump 5 sacks cement.
 Pulled casing. Mudded hole to 270'
 Set 10' rock bridge mixed and run 20 sacks cement
 Mud to 40' set 10' rock bridge with 10 sacks cement to base of cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA, KANSAS
 JAN 17 1961
 1-19-1964

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
 Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren W. Warner (Pres)
Box 364, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 19 day of January, 19 61

My commission expires 24 October 1964
Sidney D. Miller
 Notary Public.



WELL LOG

15.083.10168-00.00

OWNER J E Newman
 Suite 2005, 1700 Broadway
 Denver 2, Colorado

LOCATION
 NW NW NW
 Section 21, 22S, 23 W
 Hodgeman County, Kansas

CONTRACTOR Cherokee Drilling & Exploration Co, Inc
 P O Box 628, El Dorado, Kansas

FARM Schneider

DATE COMD November 4, 1959

DATE COMP November 22, 1959

TOTAL DEPTH 4,728½ feet 277 feet of 8 5/8" casing for surface - Cemented

FROM	TO	
0	277	Shale and shells
277	765	Gray shale
765	1,759	Shale and redbed
1,759	1,780	Anhydrite
1,780	2,090	Redbed and shal
2,090	2,665	Shale and lime
2,665	3,060	Lime
3,060	3,915	Shale and lime
3,915	4,664	Lime
4,664	4,728½	Lime and chert
	4,728½	Total Depth

I hereby certify that the foregoing is a true and correct copy of the well log for the Schneider #1 well drilled for J E Newman and completed on November 22, 1959.

CHEROKEE DRILLING & EXPLORATION CO, INC

Irvin E Thrasher, Secretary-Treasurer

STATE OF COLORADO)SS
 COUNTY OF DENVER)

Subscribed and sworn to before the undersigned a Notary Public in and for the County and State aforesaid this 20th day of September, 1962

Vera J. Burton
 Notary Public

My Commission expires September 15, 1964

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 26 1962
 CONSERVATION DIVISION
 Wichita, Kansas