


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15.083-10193.00-00  
WELL PLUGGING RECORD

P

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 18 Twp. 22S Rge. (E) 23 (W)  
Location as "NE/CNW/SW" or footage from lines. C NE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Johnson B Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 17, 19 61  
Application for plugging filed December 17, 19 61  
Application for plugging approved December 17, 19 61  
Plugging commenced December 17, 19 61  
Plugging completed December 17, 19 61  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 4715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'. Set Plug. Cemented with 25 sacks cement. Heavy mud to 35'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1961  
WICHITA, KANSAS  
CONSERVATION DIVISION

12-27-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.  
C. W. Sebitts (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1961

My commission expires September 24, 1962  
Maxine Johnson Notary Public.



15.083.10193.00.00  
ROTARY DRILLING LOG

9

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita 2, Kansas

LOCATION: JOHNSON B #1 - C NE SE, Sec. 18-22S-23W,  
Hodgeman Co., Kansas

Rotary Drilling Commenced 11-28-61  
Rotary Drilling Completed 12-17-61

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: 262' (6 jts.) 8 5/8" 20# Surface Casing cemented w/175 sacks cement.  
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
60'	Top Soil & Clay	4576'	
275'	Shale	4616'	
300'	Sand	4670'	
865'	Shale	4680'	
1038'	Red Beds	4690'	
1060'	Blaine	4696'	
1100'	Red Beds	4701'	
1135'	Shale	4706'	
1330'	Sand	4715'	
1656'	Red Beds		
1685'	Anhydrite		
2060'	Shells & Shale	<u>Slope Test</u>	
2330'	Shale, Lime & Shells	1590'	0°
2490'	Lime & Shale	2695'	0°
2925'	Lime	3555'	0°
3680'	Lime & Shale	4505'	0°
3890'	Lime, Shale & Sand		
3995'	Sand & Lime	<u>S. L. M.</u>	
4055'	Lime & Shale	1500'	
4373'	Lime	3700'	
4680'	Lime & Shale	4500'	
4715'	Mississippi R.T.D.		

RECORDED  
DEC 27 1961  
CONSERVATION DIVISION  
WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 26th day of December, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson  
Maxine Johnson Notary Public