


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 17 Twp. 22S Rge. (E) 23 (W)
Location as "NE/CNW%SW%" or footage from lines SW NE SW
Lease Owner Braden-Deem, Inc.
Lease Name Henry Novotny Well No. 3
Office Address 210 One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) SWD
Date well completed 19
Application for plugging filed May 28 1969
Application for plugging approved May 29 1969
Plugging commenced July 30 1969
Plugging completed July 30 1969
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	398	None
				5-1/2"	4669	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SWD well TD 4670 PB to 1300' and 5 1/2' casing cemented to surface.

Pumped in 1 sk hulls, 10 sks gel and 120 sks cement.
No casing pulled. 10 sks cement from 40' to surface.

Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of August, 1969

My commission expires March 21, 1970

Notary Public.

COMPANY: Tennessee Gas & Oil Company,
P.O. Box #2511, Tennessee Bldg.,
Houston, Texas.

Rotary Drilling Commenced 11-16-59

Rotary Drilling Completed 12-6-59

LOCATION: #3 Novotny
SW NE SW Sec. 17-22-23W
Hodgeman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 400' (13 Jts.) 8 5/8" 24# J-55 Smls. casing. Cemented with 300 sacks cement and 2% C.C. Cement Circulated.

146 Jts. 5 1/2" Casing set at 4699' cemented with 70 sacks pozmix & 45 sacks pozmix latex.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	surface soil
300	shale & shells
315	sand
399	shale & shells
700	shale
975	red rock & shale
1060	shale & shells
1270	sand & shale,
1620	shale & shells
1635	Anhydrite
2325	shale & shells
2750	lime & shale
2825	lime
2915	lime & shale
3100	lime
3160	lime, shale & chalk
4410	lime & shale
4452	lime, cherty
4604	lime & shale
4610	sand
4695	Mississippi
4700	shale
4700	Rotary Total Depth

Circ. for Samples:

4100'	—
4610'	—
4639'	—
4652'	—
4660'	—
4666'	—
4699'	—
4695'	—

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1969
CONSERVATION DIVISION
Wichita, Kansas

Slope Test:

1000'	00
2900'	00
2500'	00
2920'	00

S.L.M. - 3906' (correction made)

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Gerald W. Pike
Attorney-in-Fact

Gerald W. Pike, Partner

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 14th day of December, 1959, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above-written.

My commission expires: August 13, 1961

Ruth M. Sullivan
Notary Public

Ruth M. Sullivan