


Give Full Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 16 Twp. 22S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Wilcox Oil Company
Lease Name WARNER Well No. 1
Office Address Box 1440, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 13 1964
Application for plugging filed May 13 1964
Application for plugging approved May 13 1964
Plugging commenced May 13 1964
Plugging completed May 13 1964
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4788 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	412'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 720', spot 25 sacks cement. Fill hole with rotary mud to 420' and set plug, spot 25 sacks cement. Mud back to 45'. Set bridge with hulls and cap with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *Wilson Rains*
Wilson Rains, Partner
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1964

My commission expires January 8, 1968

Shirley Keck
Shirley Keck Notary Public.

15.083.00259.00.00

ROTARY DRILLING LOG

Operator: Wilcox Oil Company
No. 1 WARNER
C NE SW Sec. 16-22S-23W
Hodgeman County, Kansas

Contractor: Rains & Williamson
Oil Co.
Commenced: 4-30-64
Completed: 5-13-64

Remarks: Set 8-5/8" casing
at 412' with 185
sacks HA 5 posmix
cement.

Formations

Shale & Shells	105'
Shale	414'
Shale & Shells	750'
Shale & Red Bed	1040'
Anhydrite	1056'
Shale	1123'
D. Sand	1323'
Shale	1664'
Anhydrite	1705'
Shale	1820'
Shale & Shells	2390'
Lime & Shale	3310'
Shale & Lime	4000'
Lime & Shale	4180'
Lime & Shale & Chert	4205'
Lime	4245'
Lime & Shale	4310'
Lime & Chert	4326'
Lime & Shale	4410'
Lime	4585'
Lime & Shale & Sand	4635'
Lime & Shale	4700'
Lime & Chert	4713'
Lime	4750'
Lime & Shale & Chert	4788'
RTD (D&A)	4788'

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.


Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for
the State of Kansas, County of Sedgwick, this 15th day of May, 1964.

My Commission Expires:
January 8, 1968

