

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County, Sec. 15 Twp. 22S Rge. (E) 23 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Rains & Williamson Oil Co.

Lease Name MAUD Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-12 19 63

Application for plugging filed 12-12 19 63

Application for plugging approved 12-12 19 63


Plugging commenced 12-12 19 63

Plugging completed 12-12 19 63

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities

If a producing well is abandoned, date of last production --- 19 ---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas

Producing formation None Depth to top --- Bottom --- Total Depth of Well 4710 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	396'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 25 sacks cement at 700'. Filled hole with rotary mud to 390'. Spotted 25 sacks cement. Filled hole with rotary mud to 40 feet of base of cellar. Set plug and hulls and capped with 15 sacks cement. Job Completed at 1:15 A.M.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

12-17-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains, Partner (XXXXXX) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God:

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 63

My commission expires November 8, 1966

Sherry Gish Notary Public.

15.083.10218.00.00  
ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co. et al  
#1 MAUD, C NE SW  
Section 15-22S-23W  
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson  
Oil Co.  
COMMENCED: 11-29-63  
COMPLETED: 12-12-63

Remarks: Set 8-5/8" surface  
casing at 395' w/  
175 sacks cement

**Formations:**

Surface Clay	40'
Shale	395'
Shale and Shells	675'
Sand	695'
Shale and Red Bed	915'
Anhydrite	930'
Shale and Shells	1030'
D. Sand	1217'
Shale and Red Bed	1562'
Anhydrite	1595'
Shale	1830'
Shale and Shells	2305'
Line and Shale	3045'
Shale and Line	3335'
Line and Shale	3425'
Shale and Line	3945'
Line and Shale	4035'
Line	4070'
Line and Shale	4180'
Line	4270'
Line and Shale	4410'
Line	4475'
Line and Shale	4605'
Line	4710'
Rotary Total Depth (D&A)	4710'

We certify the above log is  
true and correct to the best of  
our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

  
Wilson Rains  
Partner

Subscribed and sworn to before me, a  
Notary Public in and for the State of  
Kansas, County of Sedgwick, this 16th  
day of December, 1963.

  
Sherry Gish Notary Public

My Commission Expires:  
November 8, 1966

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION  
Wichita, Kansas