

STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Believer Report to:  
 Conservation Division  
 State Corporation Commission  
 211 No. Broadway  
 Wichita, Kansas

15.083.00073.00.00  
 WELL PLUGGING RECORD

NORTH

	X		

Locate well correctly on above Section Plat

Hodgeman County, Sec. 10 Twp. 22S Rge. (E) 23W (W)

Location as "NE/CNW/SE/SW" or footage from lines C-SE-NW  
 Lease Owner Sunray DX Oil Company  
 Lease Name Maud Armstrong Well No. 1  
 Office Address 321 West Douglas, Wichita 2, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed June 1, 19 62  
 Application for plugging approved June 5, 19 62  
 Plugging commenced June 1, 19 62  
 Plugging completed June 1, 19 62  
 Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4795 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi Osage	Water	4577'	4621'	8 5/8"	270'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole with mud from Total Depth (4795') to 300'. Dump 25 sacks of cement from 300' to 225'. Fill hole with mud from 225' to 40'. Dump 10 sacks of cement from 40' to surface, and cap well.

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 11 1962

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Stickle Drilling Company  
 Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Gary W. Pierce (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce  
321 West Douglas, Wichita 2, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 62

My commission expires July 17, 1965  
Margaret Myers Notary Public.

15.083.00073.00.02


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SUNRAY DX OIL CO.  
Farm- Maude Armstrong No. 1

SEC. 10 T. 22 R. 23W  
C SE NW

Total Depth. 4795'  
Comm. 5-19-62 Comp. 6-1-62  
Shot or Treated.  
Contractor. Stickle Drilling Co.  
Issued. 9-29-62

County Hodgeman  
KANSAS



CASING:  
8" 270' cem w/200 ex.

Elevation. 2330' DF

Production. Dry

Figures Indicate Bottom of Formations.

clay, sand & shale	160
shale & clay	272
black shale & red bed	985
red bed & sand	1455
red bed & shale	2120
shale & shells	2285
lime & shale	2445
lime	2567
lime & shale	2583
lime	2945
lime & shale	3095
shale & lime	3200
lime & shale	3439
shale, chalk & lime	3605
shale	3743
shale & lime	3890
lime	4186
lime & shale	4272
lime	4315
shale & lime	4403
lime & shale	4479
lime	4630
lime & chert	4662
chert & lime	4737
chert	4757
lime & chert	4795
Total Depth	

TOPS: LOG	
Anhydrite	1556
Heebner	3884
Lansing	3933
Base Kansas City	4244
Cherokee Shale	4464
Warsaw	4577
Osage	4621
Kinderhook	4699
Viola	4726