


15.083.00023.00.00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Hodgeman County, Sec. 9 Twp. 22S Rge. (E) 23 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW  
Lease Owner Pickrell Drilling Company  
Lease Name Campbell "C" Well No. 2  
Office Address 705 Fourth National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-16-61 March 16, 19 61  
Application for plugging filed March 16, 19 61  
Application for plugging approved March 16, 19 61  
Plugging commenced March 16, 19 61  
Plugging completed March 16, 19 61  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 S. Main, St. John, Kans.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	291'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 270'/set plug. Cement with 15 sks cement. Heavy mud to 35'/set plug. Cement to bottom of cellar with 10 sks cement. Plug rat hole with 2 sks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1961

CONSERVATION DIVISION  
Wichita, Kansas

3-29-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 28th day of March, 19 61

My commission expires March 7, 1964  
Marilyn A. Davis Notary Public.



15.083.00023.00.00

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita 2, Kansas

Rotary Drilling Commenced 3-2-61

Rotary Drilling Completed 3-16-61

LOCATION: CAMPBELL "C" #2 - C SE SW 9-22S-23W, Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Ran 7 jts. 20# 8 5/8" Surface Casing. Set @ 291' w/175 sks. cement.  
Circ.  
D & A, No oil string.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

<p>33' 145' 292' 375' 400' 800' 815' 920' 1025' 1040' 1110' 1310' 1643' 1665' 2375' 2400' 2850' 3465' 3528' 3650' 3775' 3840' 3965' 4100' 4140' 4183' 4240' 4645' 4700'</p>	<p>Soil clay Post rock, clay Shale, shells Shale Sand Shale Shells, red bed Red bed, shale Shale, shells Blaine Red bed, shale Sand, shale Red bed, shale Anhydrite Shale, shells Lime, shale Lime Lime, shale Shale, lime Lime, shale Shale, sand, lime Lime, shale Shale, lime Lime, shale Lime Lime, shale Lime Lime, shale Lime Miss. T.D.</p>	<p><u>Circulate for Samples</u>  4650' 4660' 4665' 4671' 4676' 4681' 4700'  <u>Slope Test</u>  2715' 3920'  <u>S.L.M.</u>  3839'</p>
---	--	--

The undersigned, C. W. Sebitt, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
By [Signature]  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 28th day of March, 19 61, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitt, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

[Signature]  
Notary Public  
Marilyn A. Davis