

15.083.10109.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form GP-4

R WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County. Sec. 26 Twp. 22 Rge. 22 (E) (W) X
C SE SW

Location as "NE/CNW%SW%" or footage from lines

Lease Owner Imperial Oil of Kansas

Lease Name Hertel Well No. #2

Office Address Box 97, Wakeeney, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-26-63 19

Application for plugging approved 19

Plugging commenced 7-1-63 19

Plugging completed 7-5-63 19

Reason for abandonment of well or producing formation


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott

Producing formation Depth to top Bottom Total Depth of Well 4510' Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4400', mixed and ran 5 sacks cement thru dump baler.
Mixed and pumped in 40 sacks gel and 25 sacks weight mud to hold down flow of water.
Pulled 20 joints. Squeezed hole with 10 sacks gel and 200 sacks cement by Halliburton.

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer - Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of July, 19 63

My commission expires 24 October 1964 Sidney Miller Notary Public.

INVOICED
DATE 7/8/63
INV. NO. 7262-W

DRILLER'S LOG

15. 083. 10109. 00. 00

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

HERTEL NO. 2
C SE SW Sec. 26-22S-22W
Hodgeman County, Kansas

Total Depth: 4506'

Elevation: 2167 K.B.

Commenced: 5/17/63 Completed: 5/30/63

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 239' with 200 sacks cement.
Set 5-1/2" production pipe at 4509' with 175 sacks #1 Posmix.

Figures indicate bottom of formations:

Tops

Sand & Shale	660'	Heebner	3728 (-1561)
False Anhydrite	672'	Lansing	3814 (-1647)
Sand & Shale	1300'	B/Kansas City	4142 (-1975)
Anhydrite	1338'	Cherokee Shale	4322 (-2155)
Sand & Shale	1685'	Miss. (Osage)	4415 (-2248)
Shale	1995'	Kinderhook	4380 (-2313)
Shale & Lime	3930'		
Lime	4093'		
Lime & Shale	4175'		
Lime	4311'		
Lime & Shale	4370'		
Lime	4415'		
Lime & Chert	4423'		
Chert	4426'		
Lime & Chert	4429'		
Chert	4432'		
Lime & Chert	4443'		
Chert	4481'		

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1963
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

Raymond R. Dombaugh
Raymond R. Dombaugh *Ray Gordon Keen*

*Subscribed and sworn to before me this 19th day of June, 1963

My Commission Expires:

July 5, 1966

Bette J. Silcott
Bette J. Silcott Notary Public