


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County. Sec. 21 Twp. 22 Rge. 22W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
N2 N2 SE
Lease Owner Brooks Hall Oil Corporation
Lease Name Miller Well No. #1
Office Address 101 Park Ave, Suite 600, Okla City
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Oil
Date Well completed _____ 1980
Application for plugging filed _____ 1980
Application for plugging approved _____ 1980
Plugging commenced 1-28 1980
Plugging completed 2-12 1980
Reason for abandonment of well or producing formation
Depleted
If a producing well is abandoned, date of last production _____ 1980

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1331	none
				4 1/2"	4499	3496.67

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 10 sacks cement, 1 sack hulls down casing to 4000'
Pipe shot at 3700 and 3500'
Pulled pipe, 80 jts, 4 1/2' casing
Squeezed well with 35 sks - 50/50 pozmix cement with 2 1/2% added
gel, 13 sks gel, 1 sk hulls, 25 sks cement, 12 sks gel, 1 sk hulls
and 10 sks cement.

RECEIVED
FEB 21 1980
CONSERVATION DIVISION
WICHITA, KANSAS

2-21-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold, Box 698,
(Address) Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1980

Luth S. Doan
Notary Public.

My commission expires September 27, 1981

KANSAS DRILLERS LOG

COMPANY Brooks Hall Oil Corporation

SEC. 21 T. 22S R. 22W

FARM Miller

NO. 1

LOC. 330' FNL & 1320' FEL

COUNTY Hodgeman

ROTARY TOTAL DEPTH 4,500'

COMM. July 31, 1979

COMP. August 9, 1979

CONTRACTOR H-30, Inc. (Rig #2)

ISSUED August 16, 1979

4190-92
2207
1983

CASING

10 3/4"

8 5/8" Set at 1,325' cemented w/500 sxs cement

ELEVATION 2,207' K.B.

5 1/2"

4 1/2" Set at 4,499' cemented w/200 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale

775'

Shale

1,343'

Anhydrite

1,370'

Shale

1,560'

Shale and Lime

2,065'

Lime and Shale

2,155'

Shale and Lime

2,330'

Lime and Shale

2,683'

Shale and Lime

2,850'

Lime and Shale

3,255'

Shale and Lime

3,400'

Lime and Shale

3,830'

Lime

4,500'

Rotary Total Depth

4,500'

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 16th day of August, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982