

1 050682

API NUMBER 15-055-20,625-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW, SEC. 26, T 22 S, R 27 W/4

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Berger Well # 1

Operator: Falcon Exploration Inc

County Finney 162.44

Name & Address 1531 KSB Bldg.

Well Total Depth 4641 (Miss) feet

Wichita Kansas

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Co. License Number 5104

Address P.O. Box 1413 Great Bend Kansas 67530

Company to plug at: Hour: 7:00 am Day: 10 Month: November Year: 19 85

Plugging proposal received from Leroy Barron

(company name) Blue Goose Drilling Co (phone) 316-792-5633

were: To keep hole full of heavymud + spot cement plugs through drill pipe 1st plug @ the base of the anhydrite with 50sx, 2nd plug @ half the Anhydrite + 200' w/80sx 3rd plug @ the base of the surface pipe + 30' w/40sx 4th plug @ 40' with a solid bridge plug + 10sx.

Circulate Rathole w/10sx Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 am Day: 10 Month: November Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of heavymud + spotted cement plugs through drill pipe 1st plug @ 1720' w/50sx 2nd plug @ 1030' w/80sx 3rd plug @ 280' w/40sx 4th plug @ 40' w/solid bridge plug + 10sx Circulate Rathole w/10sx

Anhydrite (1700') Elevation (2600')

Remarks: Halliburton pumped 60/40 pozmix 6% gel cement
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE NOV 22 1985

NOV 18 1985

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 11120

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

N CARD MUST BE SIGNED

Starting Date: November 1, 1985
month day year

API Number 15- 055-20,625-0000

OPERATOR: License # 5316
Name Falcon Exploration Inc.
Address 1531 KSB Bldg.
City/State/Zip Wichita, KS 67202
Contact Person Mike Mitchell
Phone (316) 262-1378

C NW NW Sec 26 Twp 22 S, Rgr 27
(location) East West
4620 Ft North from Southeast Corner of Section
4620 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5104
Name Blue Goose Drilling Co.
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 660 feet.
County Finney
Lease Name Berger Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Snd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Cheyenne
Depth to Bottom of usable water 200-1000 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200 feet
Conductor pipe if any required feet
Ground surface elevation feet MSI.

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4900 feet
Projected Formation at TD Miss, a Viola
Expected Producing Formations Cherty, Cong.

This Authorization Expires 4-29-86
Approved By 10-29-85

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 10-29-85 Signature of Operator or Agent *W. A. Viola* Title President

R. H. T. DATE

Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1985

CONSERVATION DIVISION
Wichita, Kansas