

12-8-87

To: 1 050969  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,393-0000  
C NE NW, SEC. 33, T 22 S, R 27 W/EX  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name Powell Well # 1-33

Operator: Helmerich & Payne, Inc.

County Finney 15-8,11

Name &

Address P.O. Box 558

Well Total Depth 4865 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 788

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Helmerich & Payne, Inc. License Number 5293

Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 9:30 a.m. Day: 8 Month: 12 Year: 19 87

Plugging proposal received from Ken Jehlik

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 4767' Perfs at 4574-4576, 4580-4588' Elevation 2614' GL 5 1/2" squeezed at 1250' w/300 sx cement

1st plug at perfs with 25 sx cement,

2nd plug at 1800' with 25 sx cement,

3rd plug at 1200-0' with approx. 120 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30 a.m. Day: 8 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 25 sx cement, 61 barrels of mud, 25 sx cement, 8 barrels of mud and 110 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 1500 psi and shut in 1500 psi.

DEC 9 1987 12-9-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOICED (If copy is not received) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 12-9-87

INV. NO. 19240

12-8