

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00277-00-00
Spot: CSE Sec/Twnshp/Rge: 14-22S-33W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: KISNER-HORTON Well Number: 1
County: FINNEY Total Vertical Depth: 2661 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 520 WITH 350 SX CMT
Production: Size 5.5 feet: 2657 WITH 800 SX CMT
Liner: Size feet:

\$86.48

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/31/2001 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 500# HULLS & 2650' OF CMT SLURRY. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS WITH 50 SX CMT

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/31/2001 9:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2632'. PERFS AT 2562-2570, 2592-2602, 2612-2626'. PUMP 500# HULLS FOR BOTTOM PLUG. PUMPED 245 SX CMT TO FILL 5 1/2" CASING FROM 2632' TO SURFACE. PRESSURED TO 300#. HOOK ONTO BACKSIDE AND PUMP 1 BBL WATER DOWN BACKSIDE. PRESSURED TO 300# AND HELD.

RECEIVED
SEP 07 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GE. BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Jim Holland PJRT #
(TECHNICIAN)

INVOICED SEP 06 2001
DATE 9-7-01
INV. NO. 2002060429 MP