

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24845-00-00
Spot: W2NENWSW Sec/Twnshp/Rge: 8-11S-17W
2310 feet from S Section Line, 4390 feet from E Section Line
Lease Name: CARMICHAEL D Well #: 7
County: ELLIS Total Vertical Depth: 3526 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3525		225 SX
SURF	8.625	1113		490 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2017 8:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E&P, LLC DBA Phone: (785) 737-3736

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: Simpson Sand 3409' - 3411' and 3424' - 3426'.
Casing leaks at 2225'.
CIBP at 3420'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2017 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1100'. APS ran in hole with tubing to 3391'. Quality rigged to tubing and pumped 175 sx cement w/250 # hulls mixed in. Pulled tubing to 1650' and pumped 160 sx cement w/250 # hulls to circulate cement up 5 1/2" casing. Shut in 5 1/2" casing and pumped 40 sx cement to circulate up 8 5/8" casing. Pulled tubing. Rigged to 5 1/2" casing and pumped 50 sx cement to pressure up 5 1/2" and 8 5/8" casings with 250 psi. Shut in pressure 200 psi.
01/24/2017 - Topped off well with 25 sx cement.

GPS: 39.10960 -099.23758

Perfs:

INVOICED
FEB - 2 2017

Remarks: QUALITY CEMENTING CO. TICKET # 3121

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

KCC WICHITA

JAN 30 2017

RECEIVED

Form CP-2/3

JAN 24 2016