

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20835-00-01
Spot: W2SW Sec/Twnshp/Rge: 15-12S-32W
1275 feet from S Section Line, 526 feet from W Section Line
Lease Name: YOUNKIN Well #: 1
County: LOGAN Total Vertical Depth: 4781 feet

Operator License No.: 34315
Op Name: KANSAS OIL RESOURCES LLC
Address: 11944 W 95TH ST, STE 222
SHAWNEE MISSION, KS 66215

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4747		500 SX
SURF	8.625	225		160 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2016 10:30 AM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: RON GEIST Company: WILDCAT WELL SERVICE Phone: (785) 728-2040

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1700 # gel and 600 # hulls.
8 5/8" surface casing set at 225' w/160 sx cement.
5 1/2" production casing set at 4747' w/175 sx EA2 cement.
DV Tool set at 2467' w/300 sx cement, 85 sx circulated to pit.
TD 4781', PBD 4747'.
Perforations: 4541' - 4545'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2016 11:20 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2" production casing and pumped 75 sx cement w/400 # hulls, 1700 # gel and 235 sx cement. Maximum pressure 1000 psi. Visible cement in 8 5/8" surface casing.
GPS: 39.00709N -100.86774W
Ronnie Geist (Wildcat Well Service) plugged this well for the equipment. He is a licensed plugging contractor but not a licensed oil operator, therefore, the operator could not be changed from Kansas Oil Resources.

Perfs:

Top	Bot	Thru	Comments
4541	4545		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2797

Plugged through: CSG

INVOICED
FEB - 2 2017

District: 04

Signed

Darrel Dipman

KCC WICHITA

(TECHNICIAN)

cm

JAN 30 2017

RECEIVED