

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22569-00-00
Spot: N2NWNWSE Sec/Twnshp/Rge: 8-11S-17W
2410 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ELMO Well #: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 100 SW 9TH
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3489		150 SX
SURF	8.625	1094		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2017 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC DB Phone: (785) 434-4686

Proposed Plugging Method: Ordered 480 sx 60/40 pozmix 4% gel cement, 500 # hulls and 14 sx gel.
Hit bridge at 3054'. District supervisor approved plugging from 3054'.
Arb: 3403' - 3405'
PF: 3409' - 3414'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2017 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report: _____ Perfs: _____

Perf Tech perforated at 1700' and 1075'. Ran in hole to 3054'. Pulled one joint of tubing. Swift pumped 900 # gel followed by 50 sx cement w/400 # hulls mixed in. Pulled tubing to 1650'. Swift rigged to tubing and pumped 200 sx cement w/100 # hulls to circulate cement up 5 1/2" and 8 5/8" casing. Pulled tubing. Rigged to 5 1/2" casing and pumped 54 sx cement to pressure up 5 1/2" and 8 5/8" casings with 400 psi. Shut in pressure 250 psi.

GPS: 39.10980 -099.23052

INVOICED
FEB - 2 2017

Remarks: SWIFT SERVICES TICKET # 29410

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) CM

KCC WICHITA

JAN 30 2017

RECEIVED

JAN 20 2017