

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20345-00-01
Spot: SESENE Sec/Twnshp/Rge: 1-11S-17W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: LIEB NW UNIT Well #: 2-1
County: ELLIS Total Vertical Depth: 3445 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3444		475 SX
SURF	8.625	249		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2017 9:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP: 3120'.
Perforations: 3122' - 3134, 04
Stage Collar at 1040' w/325 sx cement.
Well was previously known as the Dreiling # 1.
Casing Leaks

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2017 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

JD's ran in hole with tubing to 2992'. Junk in hole below 2992'. Quality rigged to tubing and pumped 100 sx cement w/250 # hulls. Pulled tubing to 1650'. Rigged to tubing and pumped 110 sx cement w/250 # hulls mixed in to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2" casing and pumped 20 sx cement w/300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" casing with instant pressure.


Perfs:

Remarks: QUALITY WELL SERVICE TICKET # 7322

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

C.M.

KCC WICHITA

JAN 24 2016

JAN 30 2017

RECEIVED

INVOICED
FEB - 2 2017