

1 030747

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Operator: Mid-Continent Energy Corp.  
Name & Address 120 S. Market, #518  
Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Co. License Number 5418

Address Box 1389, Great Bend 67530

Company to plug at: Hour: 4:45 p.m. Day: 12 Month: 10 Year: 19 86

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Co. (phone) 316-793-5681

were: To fill hole with heavy mud and spot cement through drill pipe Elevation 1986' GL  
Anhydrite 956'

1st plug at top of Arbuckle with 50 sx cement

2nd plug at 1100' with 50 sx cement

3rd plug at base of surface pipe plus 30' with 80 sx cement

4th plug at 40'-0' with 10 sx cement , 5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 p.m. Day: 12 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 4050' with 50 sx cement

2nd plug at 1100' with 50 sx cement

3rd plug at 700' with 80 sx cement

4th plug at 40-0' with 10 sx cement

5th plug to circulate rathole with 15 sx cement

REC  
STATE CORPORATION  
CONS. DIV. WICHITA

10-15-86

OCT 15 1986

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-15-86

Signed Steve Quinlan  
(TECHNICIAN)

INV. NO. 15173

10-12

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 10-6-86 month day year

API Number 15- 145-21,249-0000

OPERATOR: License # 5205
Name Mid-Continent Energy Corp.
Address 120 S. Market # 518
City/State/Zip Wichita, Kansas 67202
Contact Person Bradley R. Buebler
Phone 316-265-9501

C. SE NW Sec. 16. Twp. 22. S. Rg. 15. East
3300 Ft. from South Line of Section
3300 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5418
Name Allen Drilling Co.
City/State Great Bend, Kansas

Nearest lease or unit boundary line 660 feet
County Pawnee
Lease Name Robo FOX Well # 1
Ground surface elevation 1986 feet MSL

Well Drilled For: Well Class: Type Equipment:
XX Oil SWD Infield XX Mud Rotary
XX Gas Inj Pool Ext Air Rotary
OWWO Expl XX Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Surface pipe by Alternate: (X)
Depth to bottom of fresh water 200
Depth to bottom of usable water 240
Surface pipe planned to be set 260
Projected Total Depth 4000 feet
Formation Arbuckle

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
X Cementing will be done immediately upon setting production casing.
Date 9-26-86 Signature of Operator or Agent Kent R. Roberts Title Geologist

For KCC Use:
Conductor Pipe Required 260 feet Minimum Surface Pipe Required 260 feet per Alt.
This Authorization Expires 3-29-87 Approved By 9-29-86

Spudd 10-6-86 6 7/8" x 8 5/8" BJ Titan
Plug water well to ground level
PLUGGING PROPOSAL IF ABOVE IS D & A 3205X

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug number, depth, and size (sxs of). Includes handwritten notes like '50SX' and '40' to D'.

Vertical list of well completion details: PUSHER Craig Chastaban, TD 4075 FORMATION Arb., SURFACE PIPE 8 5/8 @ 677, ANHYDRITE 956 ELEVATION 1986, STARTING TIME & DATE 4:45 P.M. 10-12-86, COMPLETION TIME & DATE 9:30 PM, 1st PLUG @ 4050 FT. W/ 50 SX, 2nd PLUG @ 1100 FT. W/ 50 SX, 3rd PLUG @ 700 FT. W/ 80 SX, 4th PLUG @ 40-6 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 1 SX, WATER WELL PLUGGED W/ 5 SX, CEMENT COMPANY B.J. Titan, TECHNICIAN G.H. 60% gnd.

RECEIVED STATE COMMISSION ON CONSERVATION OCT 15 1986