

To: 1 120745
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-23 API NUMBER 15-145-20,546-0001 ⁵⁶⁴ 1832
W/2 SW NE, SEC. 16, T. 22 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 30395
Operator: Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

3300 feet from S section line
2310 feet from E section line
Lease Name Fertig (OWWO) Well # 1
County Pawnee
Well Total Depth 4250 ^{138.13} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Never Gas Well _____ Input Well _____ SWD Well _____ D&A _____
produced
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 23 Month: 10 Year: 19 92

Plugging proposal received from Dick Iannitti
(company name) Iannitti Oil Co. (phone) 316-792-1922

were: 5 1/2" at 4248' w/200 sx cement, Perfs at 3663-65'
1st plug pump 100 lbs. hulls and 25 sx cement to 3200'
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 23 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 100 lbs. hulls and 25 sx cement
to 3000',
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.
Pumping pressure 0-400 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1700' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED
DATE 11-4-92
INV. NO. 36681

Signed Dennis Rankin
(TECHNICIAN)