

1 120261

6-8

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,779-0000

NE NW NW, SEC. 15, T 22 S, R 15 W/EX

4950 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3517

Lease Name Stambaugh Well # 1

Operator: Columbian Services Corporation
Name & Address Bank IV Tower
P.O. Box 3501
Topeka, KS 66601

County Pawnee 130.26
Well Total Depth 4008 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 6 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2474

were: 4 1/2" at 3980' PBD 3791' Perfs at 3654-63'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 110 sx cement.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 6 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 2 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement

Pumping pressure 0-400 psi and shut in 100 psi.

6-13-89
RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1119' of 4 1/2" casing.
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (I'd like to observe this plugging.)

DATE 6-14-89

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 25056