

1 051398

1-28

209 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,578-0000

NW NW SW, SEC. 14, T 22 S, R 15 W/EX

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Barstow Well # 3

Operator: Woodman-Iannitti Oil Company

County Pawnee 97.01

Name & Address P.O. Box 308

Well Total Depth 2985 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 28 Month: 1 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 2983' w/175 sx cement. Perfs at 2943-47', DVD at 2171' w/100 sx cement
1st plug sand back to 2890' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

1-31-91

JAN 31 1991

Plugging Proposal Received by Steve Durrant
(TECHNICIAN), Kansas

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15 p.m. Day: 28 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 2890' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 1100 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1525' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE FEB 14 1991

Signed Richard W. Gray (TECHNICIAN)

INV. NO. 30749