

1 080503

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,460-0000

NE NW SE , SEC. 14 , T 22 S, R 15 (W)

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Barstow "A" Well # 1

Operator: F & M Oil Co., Inc.

County Pawnee 129.90

Name & Address 422 Union Center

Well Total Depth 3997 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 561

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 am Day: 26 Month: March Year: 19 86

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3996' PBTD 3947' Perfs at 3938-3944'

1st plug sand back to 3890' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:20 am Day: 26 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3890' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

DATE 4-7-86
APR 7 1986

Maximum pressure 500 psi and shut in 300 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2629' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE APR 8 1986

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 13331