

1120863 15.145.19024-0000 11-22 API NUMBER 15- Spud Date 10/3/64

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 SW NW, SEC. 14, T. 22 S, R. 15 W/E
3300 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134
Operator: Graham-Michaelis Corporation
Name & Address P.O. Box 247
Wichita, KS 67201

Lease Name Hoffman Well # 1
County Pawnee
Well Total Depth 3970 129.03 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 22 Month: 11 Year: 19 93

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

vers: 5 1/2" at 3969' w/125 sx cement, Perfs at 3634-40, 3656-64'
1st plug sand back to 3584' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 22 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3590' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 150 lbs. hulls and 150 sx cement.

Pumping pressure 0-500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (If ~~1~~ ~~2~~ ~~3~~ ~~4~~ ~~5~~ ~~6~~ ~~7~~ ~~8~~ ~~9~~ ~~10~~ ~~11~~ ~~12~~ observe this plugging.

DATE 12-3-93
INV. NO. 39339

Signed *Glenn Barlow*
STATE CORPORATION COMMISSION
RECEIVED
DEC 01 1993
TECHNICAL CONSERVATION DIVISION
Wichita, Kansas
FORM 2
Rev. 01-