

1 060582

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,301-0000
NE, SEC. 32, T 22 S, R 39 W/X
3960 feet from S section line
2550 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5249

Lease Name Walkenshaw Well # 1

Operator: Osborn Heirs Company
Name & Address: P. O. Box 17968
San Antonio, TX 78286

County Hamilton 89.25

Well Total Depth 2746 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 2:30 pm Day: 3 Month: June Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 2744' Perfs at 2713-23'

1st plug pump 2 sx hulls and 25 sx cement to bottom

Pump through 5 1/2" casing with mud between plugs

2nd plug at 1780' with 50 sx cement

3rd plug at 360' to surface with 30 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 4:30 pm Day: 3 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25' sx cement to bottom, 2nd plug at 1780' with 50 sx cement, 3rd plug at 360' to surface with 30 sx cement.

RECEIVED STATE CORPORATION COMMISSION

6-17-85 JUN 17 1985

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Common Cement by Midwest (if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 6-19-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 8603

6-3