

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-22057-00-00  
Spot: E2W2SW Sec/Twnshp/Rge: 18-31S-1W  
1320 feet from S Section Line, 4230 feet from E Section Line  
Lease Name: WAGONER Well #: 2  
County: SUMNER Total Vertical Depth: 3760 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30535</u>	PROD	5.5	3759		100 SX
Op Name: <u>HARTMAN OIL CO., INC.</u>	SURF	8.625	486		300 SX
Address: <u>10500 E BERKELEY SQ PKWY STE 100</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/10/2017 6:00 PM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Revd. from: RICK MCCONNEL Company: HARTMAN OIL CO. Phone: (620) 786-4161

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2017 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

RAN 2 3/8" TUBING TO 3715' & 5 SKS GEL & 35 SACKS OF CEMENT. PULLED TUBING TO 2000' & SPOTTED 25 SX CEMENT. LAYED OUT TUBING. PERFORATED 4 HOLES AT 550'. RAN TUBING BACK INTO CASING AND CIRCULATED CEMENT. UP 5 1/2" CASING AND UP BACKSIDE USING 170 SX COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
3760	3764		
3746	3762		
3741	3750		

Remarks: QUALITY WELL SERVICE, COMMON CEMENT. DENIED TA

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

INVOICED  
FEB 16 2017