

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-30255-00-00  
Spot: E2SWNESW Sec/Twnshp/Rge: 3-26S-8E  
1650 feet from S Section Line, 1700 feet from W Section Line  
Lease Name: BARRIER Well #: 34  
County: GREENWOOD Total Vertical Depth: 2540 feet

Operator License No.: 5697  
Op Name: JACKSON BROTHERS, L.L.C.  
Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2540		80 SX
SURF	8.625	43		35 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2016 12:00 PM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50 ft. cement plug inside 4.500" casing at 2400 - 2350 ft. 2. 50 ft. cement plug inside and outside 4.500" at 1100 - 1050 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/27/2016 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2409' pumped 25 sxs cement, pulled tubing to 1106', pumped 25 sxs cement, pulled tubing to 250' pumped 20 sxs cement, ran 1" pipe down back side to 145' pumped 42 sxs cement to surface, gel spacers between cement plugs, casing shot at 100' & 125'.

Perfs:

Top	Bot	Thru	Comments
2486	2500		
2430	2462		

RECEIVED  
KCC DIST # 3  
FEB 06 2017  
CHANUTE, KS  
MH  
KCC WICHITA  
FEB 10 2017  
RECEIVED

Remarks:  
Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

INVOICED  
FEB 16 2017