

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27749-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 29-30S-15E
2190 feet from N Section Line, 360 feet from W Section Line
Lease Name: DREWRY Well #: 5-29
County: WILSON Total Vertical Depth: 1437 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 610 S. 38TH STREET
KANSAS CITY, KS 66106

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1405		150 SX
SURF	8.625	22		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 07/11/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: PATRICK LOVE Company: LAYNE ENERGY Phone: (281) 475-2579

Proposed Plugging Method: Per KCC rules and regulations.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 07/11/2016 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was run in hole to 1400 ft. 25 sacks of cement were then spotted. The cement string was pulled to 700 ft and 10 sacks of cement spotted. The cement string was pulled to 250 ft and the well filled to surface with cement. The cement string was removed and the well topped off with 5 sacks of cement. A total of 75 sacks of portland cement were used to plug well. Gel spacers between cement.

Perfs:

KCC WICHITA

FEB 10 2017
RECEIVED

RECEIVED
KCC DIST #3
FEB 03 2017
CHANUTE, KS

AD

Remarks: THE WELLHEAD NEEDS CUT OFF BELOW PLOW DEPTH AND THE LOCATION RESTORED.

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

INVOICED
FEB 16 2017