

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19155-00-00
Spot: SESESE Sec/Twnshp/Rge: 2-16S-12W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHAUF A Well #: 5
County: BARTON Total Vertical Depth: 3342 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3336		125 SX
SURF	8.625	314		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2017 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls and 1300 # gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 790' and 325'. Ran tubing to 3260' and pumped 1300 # gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 800' and pumped 50 sx cement. Pulled tubing to 350'. Circulate cement to surface with 50 sx cement. Pulled tubing. Tied to casing and circulated cement to surface with 50 sx cement on surface pipe.

GPS: 38.68224 -098.60986

Perfs:

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

JAN 31 2017

INVOICED
FEB 16 2017

Form CP-2/3