

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19284-00-00
Spot: SENWSE Sec/Twnshp/Rge: 13-31S-8E
1924 feet from S Section Line, 1641 feet from E Section Line
Lease Name: NEUBECKER Well #: 2
County: ELK Total Vertical Depth: 2047 feet

Operator License No.: 30917
Op Name: NEUBECKER, DWIGHT E.
Address: PO BOX 101411
FORT WORTH, TX 76185

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2047		0 SX
SURF	8.625	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: DWIGHT NEUBECKER Company: _____ Phone: (817) 942-1440

Proposed Plugging Method: Surface and production cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 12/16/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1900' gelled hole and spotted 5 sack plug. Pulled up to 1200' and spotted 5 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" back into 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 25 sacks of cement were used to plug this well.

Top	Bot	Thru	Comments
1900	1950		


RECEIVED
KCC DIST # 3
FEB 07 2017
CHANUTE, KS
DS
KCC WICHITA
FEB 10 2017

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT TO OPERATOR.

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)

Form CP-2/3

INVOICED

FEB 16 2017

RECEIVED