

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22102-00-00  
Spot: SESESE Sec/Twnshp/Rge: 13-31S-8E  
362 feet from S Section Line, 359 feet from E Section Line  
Lease Name: NEUBECKER Well #: 4  
County: ELK Total Vertical Depth: 2620 feet

Operator License No.: 30917  
Op Name: NEUBECKER, DWIGHT E.  
Address: PO BOX 101411  
FORT WORTH, TX 76185

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2620		0 SX
SURF	8.625	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/03/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: DWIGHT NEUBECKER Company: \_\_\_\_\_ Phone: (817) 942-1440

Proposed Plugging Method: Surface and production cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 01/04/2017 12:00 AM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 2000' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 1200'. Ran 1" back into 1200' and spotted 10 sack plug. Pulled 1". Stretched casing and pulled it into at 400'. Pulled casing out. Ran 1" back into 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 195 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
2400	2610		

RECEIVED  
KCC DIST # 3  
FEB 07 2017  
CHANUTE, KS

DS  
KCC WICHITA  
FEB 10 2017  
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST RECEIVED BY OPERATOR.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
FEB 16 2017

Form CP-2/3